

## TILT PANEL REPORT

PROJECT : LOT 2 PROSPECT PLACE BERRINBA

Page: 1

Date: 16.05.2008

Panel Mark	Qty	Thickness	Net Area(Sq M)	Volume(M3)	Weight(Tonnes)
CP1	1	150	44.44	6.67	16.33
CP2	1	150	55.86	8.38	20.53
CP3	1	150	55.86	8.38	20.53
CP4	1	150	55.86	8.38	20.53
CP5	1	150	44.44	6.67	16.33
CP6	1	150	56.57	8.49	20.79
CP7	1	150	58.48	8.77	21.49
CP8	1	150	54.10	8.11	19.88
CP9	1	150	47.30	7.09	17.38
CP10	1	170	75.04	12.76	31.26
CP11	1	170	58.83	10.00	24.50
CP12	1	150	40.99	6.15	15.06
CP13	1	150	23.24	3.49	8.54
CP14	1	150	55.86	8.38	20.53
CP15	1	150	29.46	4.42	10.83
CP16	1	150	29.46	4.42	10.83
CP17	1	150	42.20	6.33	15.51
CP18	1	170	58.83	10.00	24.50
CP19	1	170	63.01	10.71	26.24
CP20	1	170	66.14	11.24	27.55
CP21	1	170	63.01	10.71	26.24
CP22	1	170	58.83	10.00	24.50
CP23	1	150	27.54	4.13	10.12
CP24	1	150	9.85	1.48	3.62
CP25	1	150	2.04	0.31	0.75
CP26	1	150	8.26	1.24	3.03
CP27	1	150	8.96	1.34	3.29
CP28	1	150	5.67	0.85	2.08
CP29	1	150	32.26	4.84	11.86
CP30	1	150	14.59	2.19	5.36
CP31	1	150	9.71	1.46	3.57
CP32	1	150	14.59	2.19	5.36
Total for	32	Panels:	1271.31	199.57	488.95